

Sample Trade Breakdown

APP APPLIANCES		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
APP	CTG	Detach & Reset Cooktop - gas 1.000 EA	1.45	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	DWRS	Install Dishwasher - Reset and attach supply line 1.000 EA	2.24	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	GDRS	Garbage disposer - Detach & reset 1.000 EA	1.32	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	HD>	Detach & Reset Range hood - oversized 1.000 EA	0.85	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	MWSRS	Microwave oven - over range type - Detach & reset 1.000 EA	1.15	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	OVBID	Detach & Reset Built-in double oven 1.000 EA	1.97	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	RFMI+	Detach & Reset Wine Refrigerator - compact (under counter) - Detach and Reset 1.000 EA	0.99	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	RFRS	Refrigerator - Remove & reset 1.000 EA	0.99	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
APP	RFWLRS	Refrig. water line - Disconnect & reconnect 1.000 EA	0.58	\$14.24	\$1.10	\$15.34
		Kitchen		1.000 EA		
TOTAL APPLIANCES			11.54	\$14.24	\$1.10	\$15.34

CAB CABINERY		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CAB	BIDITM	Cabinetry Note 1.000 EA	0.00	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		

Sample Trade Summary

11/20/2019 9:13 PM

CAB CABINETRY		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CAB	CROWN+	Add for prefinished crown molding - w/detail per LF 16.000 LF	0.61	\$151.68	\$11.76	\$163.44
	Kitchen			16.000 LF		
CAB	CTDK	Countertop subdeck - plywood 77.140 SF	1.76	\$82.54	\$6.40	\$88.94
	Kitchen			77.140 SF		
CAB	CTGE	Add on Granite or Marble - edge treatment 45.000 LF	11.25	\$0.00	\$0.00	\$0.00
	Kitchen			45.000 LF		
CAB	CTGM	Countertop - Granite 6" backsplash 6.000 SF	2.61	\$156.00	\$12.09	\$168.09
	Kitchen			6.000 SF		
CAB	CTGM	Countertop - Granite Island 45.140 SF	19.63	\$1,173.64	\$90.96	\$1,264.60
	Kitchen			45.140 SF		
CAB	CTGM	Countertop - Granite Main Lower Cabs 32.000 SF	13.91	\$832.00	\$64.48	\$896.48
	Kitchen			32.000 SF		
CAB	CTGM	Countertop - Granite Stove Backsplash 16.670 SF	7.25	\$433.42	\$33.59	\$467.01
	Kitchen			16.670 SF		
CAB	CTGMSD	Add on for undermount sink cutout & polish - double basin 1.000 EA	3.00	\$0.00	\$0.00	\$0.00
	Kitchen			1.000 EA		
CAB	CUB++	Custom cabinets - base units - Premium grade 19.000 LF	11.62	\$11,178.46	\$866.33	\$12,044.79
	Kitchen			19.000 LF		
CAB	CUFH++	Custom cabinets - full height units - Premium grade 6.000 LF	4.44	\$4,404.00	\$341.31	\$4,745.31
	Kitchen			6.000 LF		
CAB	CUW42++	Custom cabinets - wall units - 42" tall - Premium grade 16.000 LF	9.36	\$6,321.76	\$489.94	\$6,811.70
	Kitchen			16.000 LF		
CAB	DSLFS	Cabinet drawer slides - full ext. soft close 18.000 EA	1.93	\$543.78	\$42.14	\$585.92

Sample Trade Summary

11/20/2019 9:13 PM

CAB CABINETRY

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
	Kitchen		18.000 EA		
CAB KNPLRS	Cabinet knobs or pulls - Detach & reset				
	43.000 EA	1.32	\$0.00	\$0.00	\$0.00
	Kitchen		43.000 EA		
CAB PLY++	Cabinet panels - side, end, or back - Premium grade				
	100.000 SF	10.00	\$1,325.00	\$102.69	\$1,427.69
	Kitchen		100.000 SF		
CAB TK	Toe kick - pre-finished wood - 1/2"				
	26.000 LF	1.56	\$110.76	\$8.58	\$119.34
	Kitchen		26.000 LF		
CAB TRASHBN	Add for pull out trash bin				
	1.000 EA	0.00	\$72.00	\$5.58	\$77.58
	Kitchen		1.000 EA		
TOTAL CABINETRY		100.26	\$26,785.04	\$2,075.85	\$28,860.89

CLN CLEANING

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CLN FINALR	Final cleaning - construction - Residential				
	1,373.000 SF	8.04	\$0.00	\$0.00	\$0.00
	General Items		1,373.000 SF		
TOTAL CLEANING		8.04	\$0.00	\$0.00	\$0.00

CON CONTENT MANIPULATION

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CON LAB	Content Manipulation charge - per hour				
	1.000 HR	1.00	\$0.00	\$0.00	\$0.00
	Hallway		1.000 HR		
CON ROOM	Contents - move and reset to paint				
	1.000 EA	1.36	\$0.00	\$0.00	\$0.00
	Office		1.000 EA		
CON ROOM<	Contents - move out then reset - Small room				
	1.000 EA	1.02	\$0.00	\$0.00	\$0.00
	Mud Room		1.000 EA		
TOTAL CONTENT MANIPULATION		3.39	\$0.00	\$0.00	\$0.00

Sample Trade Summary

11/20/2019 9:13 PM

CPS CONT: PACKING,HANDLNG,STORAGE

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CPS	BX	Provide box, packing paper & tape - medium size				
		33.000 EA	0.00	\$103.95	\$8.05	\$112.00
		Kitchen		20.000 EA		
		Great Room		5.000 EA		
		Front Room		8.000 EA		
CPS	BX<	Provide box, packing paper & tape - small size				
		26.000 EA	0.00	\$59.02	\$4.58	\$63.60
		Pantry		8.000 EA		
		Great Room		10.000 EA		
		Front Room		8.000 EA		
CPS	BXMIR	Provide mirror/picture box, packing paper & tape				
		15.000 EA	0.00	\$115.80	\$8.97	\$124.77
		Front Room		15.000 EA		
CPS	BXPF	Provide picture-frame box, packing paper & tape				
		8.000 EA	0.00	\$49.52	\$3.84	\$53.36
		Great Room		8.000 EA		
CPS	BXTV	Provide TV box, packing paper & tape				
		1.000 EA	0.00	\$18.26	\$1.42	\$19.68
		Great Room		1.000 EA		
CPS	LAB	Inventory, Packing, Boxing, and Moving charge - per hour				
		15.500 HR	15.50	\$0.00	\$0.00	\$0.00
		Kitchen		4.000 HR		
		Pantry		1.500 HR		
		Great Room		5.000 HR		
		Front Room		5.000 HR		
CPS	PIANO	Piano skid board - per month				
		1.000 MO	0.00	\$0.00	\$0.00	\$0.00
		Front Room		1.000 MO		
CPS	STOPCD	Job-site cargo container - pick up/del. (each way) 16'-40'				
		2.000 EA	0.00	\$0.00	\$0.00	\$0.00
		General Items		2.000 EA		
CPS	STOPM<	Job-site moving/storage container - 16' long - per month				
		1.000 MO	0.00	\$0.00	\$0.00	\$0.00
		General Items		1.000 MO		
TOTAL CONT: PACKING,HANDLNG,STORAGE			15.50	\$346.55	\$26.86	\$373.41

Sample Trade Summary

11/20/2019 9:13 PM

DMO GENERAL DEMOLITION

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
CAB CTDK	Remove Countertop subdeck - plywood				
	77.140 SF	1.04	\$0.00	\$0.00	\$0.00
	Kitchen		77.140 SF		
CAB CTGM	Remove Countertop - Granite 6" backsplash				
	6.000 SF	0.65	\$0.00	\$0.00	\$0.00
	Kitchen		6.000 SF		
CAB CTGM	Remove Countertop - Granite Island				
	45.140 SF	4.87	\$0.00	\$0.00	\$0.00
	Kitchen		45.140 SF		
CAB CTGM	Remove Countertop - Granite Main Lower Cabs				
	32.000 SF	3.45	\$0.00	\$0.00	\$0.00
	Kitchen		32.000 SF		
CAB CTGM	Remove Countertop - Granite Stove Backsplash				
	16.670 SF	1.80	\$0.00	\$0.00	\$0.00
	Kitchen		16.670 SF		
CAB CUB++	Remove Custom cabinets - base units - Premium grade				
	19.000 LF	2.85	\$0.00	\$0.00	\$0.00
	Kitchen		19.000 LF		
CAB CUFH++	Remove Custom cabinets - full height units - Premium grade				
	6.000 LF	1.08	\$0.00	\$0.00	\$0.00
	Kitchen		6.000 LF		
CAB CUW42++	Remove Custom cabinets - wall units - 42" tall - Premium grade				
	16.000 LF	2.40	\$0.00	\$0.00	\$0.00
	Kitchen		16.000 LF		
CAB DSLFS	Remove Cabinet drawer slides - full ext. soft close				
	18.000 EA	0.60	\$0.00	\$0.00	\$0.00
	Kitchen		18.000 EA		
CAB PLY++	Remove Cabinet panels - side, end, or back - Premium grade				
	100.000 SF	3.89	\$0.00	\$0.00	\$0.00
	Kitchen		100.000 SF		
CAB TK	Remove Toe kick - pre-finished wood - 1/2"				
	26.000 LF	0.97	\$0.00	\$0.00	\$0.00
	Kitchen		26.000 LF		
DMO DUMP	Dumpster load - Approx. 20 yards, 4 tons of debris				
	1.000 EA	0.00	\$0.00	\$0.00	\$0.00
	General Items		1.000 EA		

Sample Trade Summary

11/20/2019 9:13 PM

DMO GENERAL DEMOLITION

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
DRY	1/2-	Remove 1/2" drywall - hung, taped, ready for texture				
		30.000 SF	0.25	\$0.00	\$0.00	\$0.00
		Kitchen				
				30.000 SF		
ELE	110	Remove 110 volt copper wiring run, box and outlet				
		3.000 EA	0.32	\$0.00	\$0.00	\$0.00
		Kitchen				
				3.000 EA		
ELE	SECP	Remove Security system - control panel and keypad detach and reset				
		1.000 EA	0.08	\$0.00	\$0.00	\$0.00
		General Items				
				1.000 EA		
FCC	EDGE	Remove Carpet -transition strip @ laminate				
		12.000 LF	0.18	\$0.00	\$0.00	\$0.00
		Office				
				12.000 LF		
FCW	LAM+	Remove Laminate - simulated wood flooring - High grade				
		878.960 SF	20.60	\$0.00	\$0.00	\$0.00
		Pantry				
				15.500 SF		
		Great Room				
				476.080 SF		
		Hallway				
				85.310 SF		
		Mud Room				
				31.000 SF		
		Hall to Bedrooms				
				24.750 SF		
		Front Room				
				142.400 SF		
		Office Hallway				
				69.100 SF		
		Hall to Rooms				
				34.820 SF		
FCW	LAM+	Remove Laminate - simulated wood flooring				
		55.000 SF	1.29	\$0.00	\$0.00	\$0.00
		Kitchen				
				55.000 SF		
FNC	CBL	Remove Corbel - wood - 2" to 4" wide				
		5.000 EA	0.62	\$0.00	\$0.00	\$0.00
		Kitchen				
				5.000 EA		
FNC	SHOE	Remove Base shoe				
		179.930 LF	0.60	\$0.00	\$0.00	\$0.00
		Pantry				
				12.330 LF		
		Great Room				
				57.330 LF		
		Hallway				
				22.360 LF		
		Mud Room				
				15.500 LF		
		Hall to Bedrooms				
				12.330 LF		
		Front Room				
				27.420 LF		

Sample Trade Summary

11/20/2019 9:13 PM

DMO GENERAL DEMOLITION

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
		Office Hallway		17.830 LF		
		Hall to Rooms		14.830 LF		
LIT	ARCH+	Remove Under-cabinet lighting				
		1.000 EA	0.28	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
PLM	SNKD++	Remove Sink - double - Premium grade undermount				
		1.000 EA	0.40	\$0.00	\$0.00	\$0.00
		Kitchen		1.000 EA		
TOTAL GENERAL DEMOLITION			48.22	\$0.00	\$0.00	\$0.00

DOR DOORS

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
DOR	DOR-RS	Interior door - Detach & reset - slab only				
		2.000 EA	0.53	\$0.00	\$0.00	\$0.00
		Pantry		2.000 EA		
TOTAL DOORS			0.53	\$0.00	\$0.00	\$0.00

DRY DRYWALL

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
DRY	1/2-	1/2" drywall - hung, taped, ready for texture				
		30.000 SF	0.49	\$14.10	\$1.09	\$15.19
		Kitchen		30.000 SF		
DRY	MN-A	Drywall labor minimum				
		1.000 EA	0.00	\$0.00	\$0.00	\$0.00
		Labor Minimums Applied		1.000 EA		
DRY	TEX	Texture drywall - light hand texture				
		30.000 SF	0.18	\$1.50	\$0.12	\$1.62
		Kitchen		30.000 SF		
TOTAL DRYWALL			0.67	\$15.60	\$1.21	\$16.81

ELE ELECTRICAL

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
ELE	110	110 volt copper wiring run, box and outlet				
		3.000 EA	1.63	\$31.83	\$2.47	\$34.30

Sample Trade Summary

11/20/2019 9:13 PM

ELE ELECTRICAL		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
		Kitchen		3.000 EA		
ELE	SECP	Security system - control panel and keypad detach and reset				
		1.000 EA	3.68	\$178.39	\$13.83	\$192.22
		General Items		1.000 EA		
TOTAL ELECTRICAL			5.31	\$210.22	\$16.30	\$226.52

FCC FLOOR COVERING - CARPET		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
FCC	EDGE	Carpet -transition strip @ laminate				
		12.000 LF	0.22	\$15.12	\$1.17	\$16.29
		Office		12.000 LF		
TOTAL FLOOR COVERING - CARPET			0.22	\$15.12	\$1.17	\$16.29

FCW FLOOR COVERING - WOOD		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
FCW	LAM+	Laminate - simulated wood flooring - High grade				
		878.960 SF	34.70	\$3,735.60	\$289.51	\$4,025.11
		Pantry		15.500 SF		
		Great Room		476.080 SF		
		Hallway		85.310 SF		
		Mud Room		31.000 SF		
		Hall to Bedrooms		24.750 SF		
		Front Room		142.400 SF		
		Office Hallway		69.100 SF		
		Hall to Rooms		34.820 SF		
FCW	LAM+	Laminate - simulated wood flooring - High grade				
		266.830 SF	10.53	\$1,134.03	\$87.89	\$1,221.92
		Kitchen		266.830 SF		
TOTAL FLOOR COVERING - WOOD			45.23	\$4,869.63	\$377.40	\$5,247.03

FEE PERMITS AND FEES		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
FEE	BID	PERMITS AND FEES- open item as incurred				
		1.000 EA	0.00	\$0.00	\$0.00	\$0.00

Sample Trade Summary

11/20/2019 9:13 PM

FEE	PERMITS AND FEES	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
	General Items			1.000 EA		
TOTAL PERMITS AND FEES			0.00	\$0.00	\$0.00	\$0.00

FNC	FINISH CARPENTRY / TRIMWORK	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
FNC	CBL	Corbel - wood - 2" to 4" wide 5.000 EA	1.60	\$247.55	\$19.19	\$266.74
	Kitchen			5.000 EA		
FNC	SHOE	Base shoe 179.930 LF	1.91	\$75.58	\$5.85	\$81.43
	Pantry			12.330 LF		
	Great Room			57.330 LF		
	Hallway			22.360 LF		
	Mud Room			15.500 LF		
	Hall to Bedrooms			12.330 LF		
	Front Room			27.420 LF		
	Office Hallway			17.830 LF		
	Hall to Rooms			14.830 LF		
FNC	SHOE	Base shoe 29.500 LF	0.31	\$12.39	\$0.96	\$13.35
	Kitchen			29.500 LF		
TOTAL FINISH CARPENTRY / TRIMWORK			3.82	\$335.52	\$26.00	\$361.52

FNH	FINISH HARDWARE	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
FNH	TVRS	TV Brackets - Wall or ceiling mounted - Detach & reset 1.000 EA	1.42	\$0.00	\$0.00	\$0.00
	Great Room			1.000 EA		
TOTAL FINISH HARDWARE			1.42	\$0.00	\$0.00	\$0.00

HVC	HEAT, VENT & AIR CONDITIONING	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
HVC	REGRS	Heat/AC register - Mechanically attached - Detach & reset 3.000 EA	0.41	\$0.00	\$0.00	\$0.00

Sample Trade Summary

11/20/2019 9:13 PM

HVC HEAT, VENT & AIR CONDITIONING

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
	Kitchen			1.000 EA		
	Great Room			2.000 EA		
HVC	TSRS	Thermostat - Detach & reset				
		1.000 EA	0.46	\$0.00	\$0.00	\$0.00
	Office Hallway			1.000 EA		
TOTAL HEAT, VENT & AIR CONDITIONING			0.87	\$0.00	\$0.00	\$0.00

LAB LABOR ONLY

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
LAB	SUPERR	Residential Supervision / Project Management - per hour				
		30.000 HR	30.00	\$0.00	\$0.00	\$0.00
	General Items			30.000 HR		
TOTAL LABOR ONLY			30.00	\$0.00	\$0.00	\$0.00

LIT LIGHT FIXTURES

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
LIT	ARCH+	Under-cabinet lighting				
		1.000 EA	0.73	\$340.90	\$26.42	\$367.32
	Kitchen			1.000 EA		
LIT	RCTRS	Recessed light fixture - Detach & reset trim only				
		10.000 EA	0.71	\$0.00	\$0.00	\$0.00
	Kitchen			6.000 EA		
	Great Room			4.000 EA		
LIT	RS	Light fixture - Detach & reset				
		3.000 EA	1.48	\$0.00	\$0.00	\$0.00
	Kitchen			3.000 EA		
TOTAL LIGHT FIXTURES			2.92	\$340.90	\$26.42	\$367.32

MUS MUSICAL INSTRUMENTS & EQUIP.

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
MUS	PNAG	Piano - Acoustic Grand / Baby Grand				
		1.000 EA	0.00	\$450.00	\$34.88	\$484.88
	Front Room			1.000 EA		

Sample Trade Summary

11/20/2019 9:13 PM

MUS MUSICAL INSTRUMENTS & EQUIP.

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
TOTAL MUSICAL INSTRUMENTS & EQUIP.		0.00	\$450.00	\$34.88	\$484.88

PLM PLUMBING

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
PLM FAU	Detach & Reset Sink faucet - Kitchen 1.000 EA	0.98	\$0.00	\$0.00	\$0.00
	Kitchen		1.000 EA		
PLM SNKD++	Sink - double - Premium grade undermount 1.000 EA	0.95	\$583.95	\$45.26	\$629.21
	Kitchen		1.000 EA		
TOTAL PLUMBING		1.94	\$583.95	\$45.26	\$629.21

PNT PAINTING

	UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
PNT BCS1SP	Seal & paint baseboard w/cap &/or shoe - two coats 139.770 LF	2.88	\$29.34	\$2.27	\$31.61
	Kitchen		29.500 LF		
	Hallway		22.360 LF		
	Mud Room		15.500 LF		
	Hall to Bedrooms		12.330 LF		
	Front Room		27.420 LF		
	Office Hallway		17.830 LF		
	Hall to Rooms		14.830 LF		
PNT BCS>1SP	Seal & paint baseboard w/cap &/or shoe, oversized- 2 coats 12.330 LF	0.27	\$3.21	\$0.25	\$3.46
	Pantry		12.330 LF		
PNT CBLS	Stain & finish corbel 5.000 EA	1.47	\$3.75	\$0.29	\$4.04
	Kitchen		5.000 EA		
PNT DOR1	Paint door slab only - 1 coat (per side) 6.000 EA	1.58	\$25.86	\$2.01	\$27.87
	Pantry		4.000 EA		
	Hallway		2.000 EA		
PNT DORT>1	Paint door/window trim & jamb - Large - 1 coat (per side) 2.000 EA	0.56	\$6.64	\$0.52	\$7.16

Sample Trade Summary

11/20/2019 9:13 PM

PNT PAINTING		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
		Pantry		1.000 EA		
		Hallway		1.000 EA		
PNT	MASKFL	Floor protection - self-adhesive plastic film				
		104.280 SF	0.70	\$12.52	\$0.97	\$13.49
		Stairs		60.720 SF		
		Upper Stairs		43.560 SF		
PNT	MASKLF	Mask and prep for paint - plastic, paper, tape (per LF)				
		275.580 LF	4.13	\$63.39	\$4.93	\$68.32
		Great Room		110.500 LF		
		Mud Room		22.330 LF		
		Hall to Bedrooms		17.330 LF		
		Front Room		38.420 LF		
		Stairs		21.670 LF		
		Upper Stairs		7.170 LF		
		Office		15.000 LF		
		Office Hallway		20.830 LF		
		Hall to Rooms		22.330 LF		
PNT	MASKSFC	Floor protection - corrugated cardboard and tape				
		123.080 SF	0.62	\$23.38	\$1.81	\$25.19
		Office		123.080 SF		
PNT	P	Paint long wall opposite island- one coat				
		94.500 SF	0.67	\$10.40	\$0.81	\$11.21
		Kitchen		94.500 SF		
PNT	P	Paint walls and ceiling - one coat				
		1,389.690 SF	9.91	\$152.87	\$11.86	\$164.73
		Pantry		120.330 SF		
		Great Room		519.080 SF		
		Hallway		729.400 SF		
		Mud Room		11.630 SF		
		Hall to Bedrooms		9.250 SF		
PNT	P	Paint - one coat				
		1,715.110 SF	12.23	\$188.66	\$14.61	\$203.27
		Kitchen		266.830 SF		
		Front Room		658.340 SF		
		Stairs		190.560 SF		
		Upper Stairs		71.840 SF		
		Office		230.250 SF		

Sample Trade Summary

11/20/2019 9:13 PM

PNT PAINTING

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
	Office Hallway			146.290 SF		
	Hall to Rooms			151.000 SF		
PNT	PHIGH	Additional cost for high wall or ceiling - Over 14'				
		730.180 SF	0.89	\$0.00	\$0.00	\$0.00
	Front Room			658.340 SF		
	Upper Stairs			71.840 SF		
PNT	SHOE	Seal & paint base shoe or quarter round				
		57.330 LF	0.53	\$5.73	\$0.44	\$6.17
	Great Room			57.330 LF		
PNT	SP2	Seal/prime then paint the surface area twice (3 coats)				
		40.000 SF	0.54	\$10.00	\$0.78	\$10.78
	Kitchen			40.000 SF		
TOTAL PAINTING			36.98	\$535.75	\$41.55	\$577.30

TIL TILE

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
TIL	SEALS	Tile/stone sealer				
		175.950 SF	1.10	\$58.06	\$4.50	\$62.56
	Kitchen			175.950 SF		
TOTAL TILE			1.10	\$58.06	\$4.50	\$62.56

TMP TEMPORARY REPAIRS

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
TMP	TLTMN	Temporary toilet - Minimum rental charge				
		1.000 EA	0.00	\$0.00	\$0.00	\$0.00
	General Items			1.000 EA		
TOTAL TEMPORARY REPAIRS			0.00	\$0.00	\$0.00	\$0.00

WDT WINDOW TREATMENT

		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
WDT	BLNDRS	Window blind - horizontal or vertical - Detach & reset				
		6.000 EA	3.29	\$0.00	\$0.00	\$0.00
	Great Room			4.000 EA		
	Front Room			2.000 EA		

[REDACTED]

Sample Trade Summary

11/20/2019 9:13 PM

WDT WINDOW TREATMENT		UNITS	HOURS	MATERIAL COST	MATERIAL TAX	MATERIAL TOTAL
WDT HWRS	Window drapery - hardware - Detach & reset					
	4.000 EA	2.19	\$0.00	\$0.00	\$0.00	
	Great Room	2.000 EA				
	Front Room	2.000 EA				
WDT SHTRRS	Interior window shutters (set) - Detach & reset					
	2.000 EA	1.21	\$0.00	\$0.00	\$0.00	
	Front Room	2.000 EA				
TOTAL WINDOW TREATMENT			6.69	\$0.00	\$0.00	\$0.00